



**EXECUTIVE DIRECTOR  
CELE QUESADA**

## **COMMISSIONERS**

REV. RONNIE LINDEN, CHAIRMAN  
DESIREE EDWARDS, VICE-CHAIRMAN  
FARHANA SWATI  
BART BRAGG  
CLONIE AMBROISE

### **HQS Move-in Inspection Checklist for Landlords**

Each unit rented to a Section 8 Voucher holder must pass a Housing Quality Standards (HQS) inspection. The checklist below is a tool for owners to prepare their unit for an HQS inspection. This checklist highlights some of the COMMON violations found during unit inspections. The items on this checklist must be working or completed **prior** to the HQS inspection. This brief listing is for purposes of information only and is not intended as a completed listing.

The unit must be empty/vacant from previous tenant.

Utilities (water, gas, electricity) must be turned on by the landlord for the completion of the inspection.

No chipping or peeling paint inside or outside the unit.

Stove must be clean and in working order and secured. (if provided by landlord)

Refrigerator must be clean and be in working order with a good door seal. (if provided by landlord)

There must be a permanently installed working heating system.

Hot and cold running water in the kitchen and bathroom(s).

There must be a shower or bathtub that works properly.

There must be a flush toilet that works, is securely mounted and does not leak.

The bathroom must have either an outside window or an exhaust fan vented to the outside.

There must not be any plumbing leaks.

There must not be any plugged drains ( please check for slow drains).

All plumbing fixtures must have P-traps to prevent sewer gas from leaking into the unit.

All ground floor windows and exterior doors shall open and close as designed and must have working locks.

Double keyed dead bolts are not permitted.

Each living space must have two means of fire egress (i.e. door & window).

All electrical outlets /switches must have cover plates and be in good working condition.

All ground fault circuit interrupters (GFCIs) must work properly.

There must not be any missing, broken, or cracked windows.

The roof must not leak. Indications of a leak are discolorations or stains on the ceiling.

The hot water heater tank must have a temperature pressure relief valve with downward discharge pipe made of galvanized steel or cooper tubing that is between six inches to eight inches from the floor or directed outside the unit (no PVC). CPVC is acceptable.

The floor covering cannot be torn or have holes that can cause someone to trip.

If there are stairs and railings, they must be secure.

Four or more exterior stairs must have handrails 34 inches to 38 inches from the ground.

Walk offs or porches 30 inches above ground must have rails 36 inches from the ground.

There must be working smoke detectors properly mounted on each level of the unit including the basement and walk up attics.

All security bars and windows must have a quick release mechanism.

All sliding glass doors must have a lock or security bar on the door that works.

All construction / rehabilitation (painting, carpet replacement, etc) must be completed.

The unit must be free from roaches or rodents.

There must be stepping stones or walkway to the unit.